

Decarbonizing Multi-Family Housing Development: Actionable Pathways to GHG Emission and Building Cost Reduction with Industrialized Construction

Shanti Pless National Renewable Energy Lab May 16, 2023

Innovate on Process to Install EE



Better Product Affordable, net-zero energy, low-carbon, and healthier

Better Process Improving productivity, quality, carbon emissions, and affordability of building construction

U.S. DOE "Advanced Building Construction"

Net-Zero Energy | Low-Carbon | Affordable | Appealing

Mission:

- Help deliver affordable, appealing, highperformance, low-carbon new buildings and retrofits at scale
- Help integrate energy efficiency solutions into highly productive U.S. construction practices for new buildings and retrofits



The Advanced Building Construction (ABC) Initiative integrates energy efficiency solutions into highly productive U.S. construction practices for new buildings and retrofits.



In short, ABC refers to retrofit and new construction approaches that combine:

Energy-efficient decarbonization

Scalable, streamlined industrialized construction

ABC: Industrializing Construction to Decarbonize Buildings

DOE's Advanced Building Construction (ABC) Initiative is focused on accelerating the decarbonization of the U.S. buildings sector through industrialized construction innovations that deliver efficient, affordable, and appealing new buildings and retrofits at scale.

Development & Demonstration

Innovate & validate appealing solutions that can achieve carbon neutrality for common and high-impact building types.



Market Transformation

Use the ABC Collaborative to communicate consumer interests and inform product design; aggregate demand; reduce risks; and establish competitive business models.

ABC Initiative Investments Focus on Technologies, Manufacturing, & Markets www.buildings.energy.gov/abc

Zero Energy Mixed Use and Multifamily: Site Built Examples



Boulder Commons

http://bouldercommons.com/ https://crej.com/news/boulder-commonsto-add-more-office-plus-apartments/



UC Davis Student Housing at Net Zero https://www.ucdavis.edu/news/west-village-expansion-start-construction https://www.ucdavis.edu/news/zero-net-energy





Zero Energy Mixed Use and Multifamily: Site Built Energy Strategies

- Near Passive House levels of insulation
 - Enhanced air tightness
- Triple pane windows
 - Electrochromic, automated shades
- Mechanical ventilation with heat recovery
- 100% LEDs
- Electric heating and hot water
 - Heat pump hot water heating
 - VRF, Air Source, Ground Source Heat Pumps
- High efficiency appliances
- Technology, tenant monitoring, and control integration
 - Smart home technology
- Unit level façade and rooftop PV
 - Battery storage and grid coordinated controls

But all struggle with cost effectiveness and affordability...



Revive Properties: https://revivefc.com/features/#energy-benefits



McKinsey&Company

MCKINSEY GLOBAL INSTITUTE REINVENTING CONSTRUCTION: A ROUTE TO HIGHER PRODUCTIVITY

FEBRUARY 2017

IN COLLABORATION WITH MCKINSEY'S CAPITAL PROJECTS & INFRASTRUCTURE PRACTICE

"America's construction industry productivity is lower today than it was in 1968."

The report calls for a global effort to modernize and upgrade the construction industry across seven broad areas:

- Reshape regulation and raise transparency
- Rewire the contractual framework
- Rethink design and engineering processes
- Improve procurement and supplychain management
- Improve on-site execution
- Infuse digital technology, new materials, and advanced automation
- Reskill the workforce

"Parts of the industry could move toward a manufacturing-inspired massproduction system, in which the bulk of a construction project is built from prefabricated standardized components off-site in a factory. Adoption of this approach has been limited thus far, although it's increasing. Examples of firms that are moving in this direction suggest that a productivity boost of five to ten times is possible."

<u>http://www.mckinsey.com/industries/capital-projects-and-infrastructure/our-insights/reinventing-construction-through-a-productivity-revolution</u>

Productivity in manufacturing has nearly doubled, whereas in construction it has remained flat.

 Overview of productivity improvement over time
 ---- Manufacturing

 Productivity (value added per worker), real, \$ 2005
 ---- Construction



\$ thousand per worker

Source: Expert interviews; IHS Global Insight (Belgium, France, Germany, Italy, Spain, United Kingdom, United States); World Input-Output Database

McKinsey&Company

BUILDING AFFORDABILITY BY BUILDING AFFORDABLY: THE CASE FOR OFF-SITE MULTIFAMILY CONSTRUCTION

POSTED ON MARCH 07, 2017 BY CAROL GALANTE AND SARA DRAPER-ZIVETZ UNDER: INCREASING THE SUPPLY OF HOU

To remain relevant and successful over time, every industry must modernize and adapt to changing demand "Inefficiencies in traditional construction industry is no except have hampered productivity and driven and revolutions in bu face rapidly changing costs up for decades, resulting in advances, and an eve timelier than ever.

How will the housing from McKinsey & Cor construction have ha increasingly costly de production of housir produce it demands cost of construction certainly a major factor.

LEKI

BERKELEY

SEARCH

60

ABOUT THE CENTER

WHO WE ARE

"Off-site construction of

efficiencies of factory

production to achieve

are built."

significant cost savings,

represents a much needed

solution to this problem. It has

the way homes and apartments

the potential to revolutionize

housing, which leverages the

increasingly costly development. Today, in many regions in the United States, the production of housing - especially infill better said, overdue, multifamily housing – has become so costly to produce it demands rents or sale prices that are unaffordable for most people."

nt

ons

ly be

port

In

0

the

are

http://ternercenter.berkeley.edu/uploads/offsite construction.pdf

Industrialized Construction



Permanent Modular Construction Partners in Multi-family

Primary Building Material: Wood





Primary Building Material: Steel

Volumetric Building Companies— Hamlet, North Carolina



Factory_OS—Vallejo, California



FullStack Modular—Brooklyn, New York

Partner with leading factories and showcase projects to achieve optimal integration of energy systems within the emerging advanced manufacturing industry for buildings



il and Construction Engineering

"How can optimal integration of a wide range of energy efficiency

strategies in industrialized construction be achieved with little or no additional cost, labor, or production time?"

This question was addressed by NREL's ICI Team along with project partners as part of the 3-year DOE funded project "Energy Efficiency in Permanent Modular Construction (EEPMC)."

Design for Manufacturing and Assembly for Energy Efficiency Strategies

- Factory installed EE strategies can simplify installation, better control scope and scheduling, enhance quality, standardize means and methods, increase construction productivity, and reduce overall construction timelines
- Quantify trade-offs for strategies that increase cost of module but reduce construction cost/time/complexity and/or eliminate on-site scope

This allows modular solutions to maximize cost effectiveness of EE solutions and leverage industrial engineering and advanced manufacturing approaches to increase productivity and reduce first cost of construction



Selected Energy Efficiency Strategies



Whole-Building Design with unit-level EE integration



Ideal NZE, low-carbon modular housing unit



EE Strategy 1: Envelope Thermal Control



Key Takeaways:

To optimally integrate the energy efficiency strategy of advanced thermal envelope, we propose that a superior quality insulation system is installed in the factory, as opposed to on-site insulation systems. Towards this end, it is critical to design an EMODoptimized factory-installed envelope system that also achieves similar thermal performance as on-site continuous exterior systems.

- Insulated studs
- SIPs
- Exterior insulation installed in factory with simple module to module detailing planned

EE Strategy 1: Case Study



Benefits from Off-site wall framing with Insulated Truss Studs (ITSs) [B]:

- Reduced labor-minutes by **63%**
- Reduced total material used by **38%**
- Reduced cost (material + labor) by **78%**

A- Baseline: Off-Site Wall framing with standard 2x6 studs
followed by on-site continuous insulation
B - Strategy: Off-Site Wall framing with ITSs and **no** on-site
continuous insulation







EE Strategy 2: Envelope Infiltration Control

Key Takeaways:



An example of in-factory airtightness improvement strategies includes the efficient use of ionized sealing. Lessons learnt from ionized sealing pilots could be leveraged to also identify opportunities for in-factory taping and caulking. We propose the following key steps to integrate the energy efficiency strategy of improved airtightness in the factory:

Use construction and manufacturing QA/QC tools and methods (such as non-destructive testing) to achieve factory-installed airtight envelope. The key steps involved are:

- Plan for a QA/QC design review of the envelope
- Test the airtightness on a set of modular units in the factory to evaluate air-barrier installation quality and develop specific strategies to ensure all modules adopt well-known standardized air-barrier details
- Test the airtightness on a representative sample of modular units at end of the factory production line to verify the airtightness value and the installation processes.

EE Strategy 2: AeroBarrier pilots at VBC factory



The key lessons learned are that airtightness starts with design and material selection, and ionized sealing should be used for fine-tuning, with additional focus on set processes, final site installed details, and final testing.

Based on the testing data prototyping and visual factory walkthrough of the station's activities and processes, there is much room to impact the overall quality of modular units positively.

| Test # | Starting ACH | Ending ACH | % Reduction | Sealing time | |
|---------|--------------|------------|-------------|--------------|--|
| Test 1 | 9.0 | 1.8 | 78% | 56 min | |
| Test 2 | 5.9 | 1.0 | 87% | 41 min | |
| Test 3 | 10.7 | 3.1 | 3.1 65% | | |
| Test 4 | 6.9 | 1.8 | 77% | 30 min | |
| Test 5 | 5.7 | 1.7 | 70% | 48 min | |
| Test 6 | 7.4 | 2.4 | 66% | 23 min | |
| Test 7 | 6.4 | 1.1 | 88% | 3% 45 min | |
| Average | 7.4 | 1.8 | 76% | 40 min | |

EE Strategy 3: Energy Exchange Pod

Can we imitate the bathroom pod approach for mechanical system?

Common for bathroom pods to be:

- Prefabricated
- installed on-site or on volumetric modular factory line

'Utility cupboards' in the UK



- Prefabricated 540 'utility cupboards' by
 Skanska UK for Battersea Project
- Took 18 man-hours to build vs 42 hours for those constructed on-site
- 44% cheaper, including factory overheads; 73% fewer defects

EE Strategy 3: Energy Exchange Pod

Key Takeaways:

A unitized Energy Exchange Pod enables:

- 1. Build -to-Stock of subsystems through chunking and prefabrication for volume production in production lines
- 2. A unitized air system for each apartment.

By following the proposed methodology, the subassembly "pod" design (fully-implemented or partially-implemented) leads to the following benefits:

- 1. Ensures proper ventilation that is hard to ensure with central ventilation systems and variable pressure across the height of a building
- 2. Limits unit to unit air cross contamination, reducing odor and acoustic pollution.

EE Strategy 3: Energy Exchange Pod





Source: VEIC

Solar Home Factory

Modular Factory Installed Solar reduces install costs

EE Strategy 5: Solar plus Storage



Each Modular Tower with 3 modules (each LVL) and rooftop PV array





ENERGY IN **MOD**ULAR **METHOD** [EMOD METHOD]

A GUIDE TO DESIGN FOR ENERGY EFFICIENCY IN INDUSTRIALIZED CONSTRUCTION OF MODULAR BUILDINGS



Shanti Pless Ankur Podder Zoe Kaufman Noah Klammer Conor Dennehy Dr. Naveen Kumar Muthumanickam Stacey Rothgeb National Renewable Energy Laboratory

Dr. Joseph Louis Oregon State University

Colby Swanson Heather Wallace Momentum Innovation Group

Cedar Blazek U.S. Department of Energy

https://www.nrel.gov/docs/fy22osti/82447.pdf

TABLE OF CONTENTS

| ACKNOWLEDGEMENTS | | | | | | |
|------------------|--|-----------|--|--|--|--|
| 0 | OVERVIEW | | | | | |
| C | HAPTER 1: INTRODUCTION | 6 | | | | |
| | Need For Industrialized Construction In The U.S. For Affordable Housing Delivery | <u>8</u> | | | | |
| | Efficiency Benefits From Industrialized Construction | 9 | | | | |
| | Towards Net-Zero Energy, Low- Carbon Modular Housing | <u>10</u> | | | | |
| | Leveraging The Advanced Energy Design Guides And Other Literature | <u>11</u> | | | | |
| CHEF | HAPTER 2: DESIGN FOR ENERGY FICIENCY IN INDUSTRIALIZED DNSTRUCTION | <u>14</u> | | | | |
| | Key Takeaways: Approaches, Tools, And Strategies | <u>16</u> | | | | |
| | Selecting A Set Of Energy Efficiency Strategies | 18 | | | | |
| | Design Of An Ideal NZE Modular Housing Solution | <u>21</u> | | | | |
| | Need For A National-Scale Shared Research Platform On EMOD METHOD | 21 | | | | |

| CHAPTER 3: ENVELOPE THERMAL CONTROL | | | | | |
|--|--|-----------|--|--|--|
| T | Key Takeaways | 29 | | | |
| | Key Benefits | 29 | | | |
| | Case Study: Time Studies And Process Modeling Evaluation With Insulated Truss Studs | <u>29</u> | | | |
| | Process Modeling Results | <u>30</u> | | | |
| CH IN | IAPTER 4: ENVELOPE FILTRATION CONTROL | <u>32</u> | | | |
| | Key Takeaways | <u>33</u> | | | |
| | Case Study: In-Factory Airtightness Improvement Pilots With Volumetric Building Companies (VBC) | 35 | | | |
| | Key Takeaways From VBC Pilot 1 | 36 | | | |
| | Key Takeaways From VBC Pilot 2 | <u>37</u> | | | |
| | Next Steps And Future Work | <u>39</u> | | | |
| CH M | APTER 5: MODULARIZATION OF | <u>40</u> | | | |
| | Key Takeaways | <u>41</u> | | | |
| | Case Study: Design Evolution With Factory OS | 42 | | | |

CHAPTER 5: MODULARIZATION OF MEP SYSTEMS (CONTD.)

| Case Study: Zero Energy Modular Bilot With VEIC | 44 |
|--|----|
| Ducting Strategy | 46 |

CHAPTER 6: SMART CONTROLS 48 INTEGRATION AND COMMISSIONING 49 Key Takeaways 49 Needs, Challenges, 49 And Benefits 49

Case Study: STRATIS IoT 50

CHAPTER 7: SOLAR PLUS STORAGE, <u>54</u> DISTRIBUTION DESIGN AND INTEGRATION

Key Takeaways, Needs,
Challenges, And Benefits55Site-Installed Centralized
Battery Systems vs. Factory-
Installed Decentralized Battery
Systems56Case Study: Solar Home
Factory57

60

CONCLUSION

Project Overview

- Blokable is developing an integrated multifamily development product that is:
 - Net-zero energy
 - Affordable AND profitable
 - Comfortable
 - Environmentally forward-thinking
 - Ahead of policy



- How can we utilize their proposed scale up to reduce both operational carbon and embodied carbon?
 - IF we built 400 units a year, what happens to the cost and performance model?
 - 10,000?

Productization, Standardization,

VS 009 ISANIEM

1º 500 SA Majvestº 500 SA

avois

AR 002 TRAVIES

SIGA

VS OOG JSBAIDW

& Manufacturing

Photo from Blokable

Methodology

Modeling the product's roadmap



- Economy of scale
- Learning effects
- Leverage vertical integration for long-term savings & affordability

- LCA model
- Scale up 1 apartment to 10k units

Methodology

Modeling product roadmap 10 years down the line

Cost model

- Productivity increase
- Economy of scale
- Reduced waste
- Operational energy savings





Energy & emissions model

- Material decarbonization
- Learning-affected waste reduction
- Grid-responsive technologies
- Operational energy savings

Apply Learning Curves to Modular scale up





Figure 4. The price of solar modules has declined by 99.6% since 1976

Figure from OurWorldinData.org

Embodied Carbon Modeling Methodology

Modeling up-front carbon of evolving product line involves policy considerations.

- Buy Clean California Act passed in July 2021 (Bill Track 50 2021)
 - Project steel-related emissions:

| Year | 2016-2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028 | 2029 | 2030 |
|---|-----------|------|------|------|------|------|------|------|------|------|
| Steel GWP (lbmCO ₂ e/lbm) | 3.05 | 2.89 | 2.72 | 2.56 | 2.4 | 2.24 | 2.08 | 1.92 | 1.76 | 1.6 |

Emissions change as Cambium emissions-factor projections change over time. Effects of decisions are weighed over the lifetime of the building.



Combined lifecycle emissions across product roadmap





Findings

Path toward decarbonization for vertically integrated developers/builders

- To reduce emissions by 60% by 2030, modular builders should incorporate the following over time:
 - Electrification and carbon-responsive GEB capability well integrated into their standard modular product
 - Factory efficiency to apply learning curves to decarb strategies
 - Waste reduction for materials with high waste factor (e.g., drywall)
 - (Structural) materials with low embodied carbon and high recycled content
 - Design (and commission) for minimal refrigerant and leakage
 - Modular HVAC systems can reduce GHG emissions by up to 20% versus centralized systems

Findings

Backdrop for moving toward building decarbonization

- With the aid of staged planning for emissions reduction of building materials, components, and operations, integrated developer-owners can create more accurate roadmaps of their own to stage a path for decarbonization
- Product design with decarbonization included at the beginning of product development lifecycle necessary to ensure we can leverage learning curves as production ramps
- **60% lifecycle carbon reduction** on a pathway of cost reduction curves

Decarbonization Roadmap & NREL Technical Report

https://nrel.gov/docs/fy22osti/81037.pd f

Google Search: "decarbonization during predevelopment"



Thank you and Questions.

Please reach out: shanti.pless@nrel.gov

We now have methods that can utilize Advanced Manufacturing and Industry 4.0 Industrial Engineering productivity improvement approaches to better integrate complex and decarbonization strategies into the design and construction process MORE cost effectively

- Requires a design that maximizes off-site and prefab approaches
- Leverages productivity gains and repeatability of processes available in factory-built modular

Next Steps:

- Scaling solutions to different regions/factories/building types
- HVAC Pod in 50 units
- ICC Off-Site MEP and Energy Code (out for first draft public review!)

NREL